



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

15-065-21498-00-00

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Gene Smith of Kelso Casing has this date requested permission to plug the following described well:

Operator's Full Name: Arrowhead Petroleum

Complete Address: 529 400 N Woodlawn - Wichita, Ko. 67208

Lease Name: Jeffers Well No. A-1

Location: CS2-NW-SE Sec. 32 Twp. 9 Rge. 22 (E)  (W)

County: Shawnee Total Depth: 3871

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Smith was instructed to plug the well as follows:

8 5/8" @ 216' w/175 sv - 4 1/2" @ 3870 w/100 sv Plug back  
to 3833' - Perfo @ 3805-9 - Sand to 3750' & dump 4  
sv cmt. - Recovered 3,027' of 4 1/2" csg. Ordered 140 sv  
50/50 permix to gel 3% cc - 25 gel - 5 hullo 8 5/8"  
plug - Pumped 4 hullo -> 13 gel -> 1 hullo -> 70 cmt -> 12  
gel R Plug -> 70 cmt max 350 # PSI - Shut in 200  
# PSI.

Very truly yours,

Rennis L. Hamel  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
8/9/82  
AUG 09 1982  
CONSERVATION DIVISION  
Wichita, Kansas

STATE  
CORP