

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1978
05-12-1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163- 20,795-00-00 (of this well)

Operator's Full Name Rains & Williamson Oil Co.

Complete Address 415 Page Ct., 220 W. Douglas, Wichita, Kansas

Lease Name Hockett Well No. 1

Location C SW NW Sec. 7 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3590

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. tools

Address License No.

Operation Completed: Hour 7:30 A Day 11 Month 5 Year 1978

The above well was plugged as follows:

RTD 3590' 8 5/8 csg set 207' cwcl50 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bis Messery
Well Plugging Supervisor

DATE 5-12-78

INV. NO. 7297-W