

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1970
CONSERVATION DIVISION
Wichita, Kansas
12-21-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20338-00-00

Operator's Full Name Abercrombie Drilling Inc.

Complete Address 801 Union Center Wichita, Kansas

Lease Name Hackerott Well No. 1

Location SE NW SE Sec. 9 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3465'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Aspen Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2:15 A Day 18 Month 12 Year 1970

The above well was plugged as follows:

RTD 3465' 8 5/8 csg set at 254' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/21/70
INV. NO. 3102-W

Signed: Leo F. Massey
Well Plugging Supervisor