

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 31 1978  
05-31-1978  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 - 20,807-00-00 (of this well)

Operator's Full Name Rains & Williamson Oil Co.

Complete Address 435 Page Ct.-220 W. Douglas, Wichita, Kansas

Lease Name Doughtery Well No. 1

Location SE SE SW Sec. 17 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3706'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 9:30 A Day 230 Month 5 Year 1978

The above well was plugged as follows:

RTD 3706' 8 5/8 csg. set 205' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

6-1-78  
7408-11

Signed: Geo. Muesel  
Well Plugging Supervisor