

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20272-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
12-01-1969

Operator's Full Name Woodman - Iannitti

Complete Address 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Dougherty Well No. 1

Location SE SE NW Sec. 17 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3550

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 12N Day 28 Month 11 Year 1969

The above well was plugged as follows:

RTD 3550' 8 5/8 csg set at 151' cwc. Cmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk cmt  
thru drill-pipe.-Heavy mud to-150'-set-cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 12/2/69  
INV. NO. 964-11