

KANSAS

Form CP-3
Rev. 6-4-68
STATE CORPORATION COMMISSION

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

NOV 30 1976
11-30-1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,660 - 00 - 00 (of this well)

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., Wichita, Kansas

Lease Name Dougherty "A" Well No. 1

Location SW SW NW Sec. 17 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3635'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 11:15 A Day 28 Month 11 Year 1976

The above well was plugged as follows:

RTD 3635' 8 5/8 csg set 205' cwc 150 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11-30-76

INV. NO. 4209-W