

15-163-19369-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1960
10-24-1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks
Location: _____ NE SE NW _____ Sec. 10 Twp. 10 Rge. 16 (E) (W)
Name of Field: _____ Total Depth: 3360

I have this date completed supervision of plugging of:

Lease Name: Mc Guire _____ Well No. 1

Operator's Full Name: Sunray Mid Continent Oil

Complete Address: Box 788 Great Bend, Kans

Plugging Contractor: Garvey Drg Co & Sun Cementing Co

Address: _____ Hays, Kans License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7:30 PM Day 15 Month 10 Year 60

The above well was plugged as follows:

8 5/8" 251' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 360', displaced 20 sax cement through drill pipe, heavy mud to 180', set cementing plug and displaced 15 sax cement through drill pipe, heavy mud to 40', set plug, hulls and filled to bottom cellar with cement.

Cementing by Sun Cementing Co.

Signed: E. J. Perry
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 10/31/60
INV. NO. 2128-W