

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
DEC 4 1967
12-04-1967
CONSERVATION DIVISION
Wichita, Kansas

15-163-20079-00-00

Operator's Full Name Kern Drilling Co., Inc.

Complete Address: 337 Union Center Bldg., Wichita, Kansas.

Lease Name Zeigler Well No. 1

Location SW SE SE Sec. 20 Twp. 10 Rge. 16 (E) (W) X

County Rooks Total Depth 3260'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Woodman-Iannitti Drlg Co.

Address: Hosington, Kansas License No.

Operation Completed: Hour 2:15 PDay 1 Month 12 Year 1967

The Above well was plugged as follows:

RDD- 3260' 8 5/8 csg set at 197' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 100 sc cem.
thru drill pipe. Heavy mud to ;80' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 12/5/67
INV. NO. 6839-U