

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1970

CONSERVATION DIVISION
Wichita, Kansas

07-27-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20317-00-00

Operator's Full Name Vincent Oil Corp.

Complete Address 625 Union Center Bldg.

Lease Name Nelson Well No. 1

Location NW SW NE Sec. 28 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3633

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:45 A Day 26 Month 7 Year 1970

The above well was plugged as follows:

RTD 3633' 8 5/8 csg set at 170' cwc Cmt. Mat. 100 sk reg poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. M... ..
Well Plugging Supervisor

DATE 7/27/70
INV. NO. 2288-W