

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-30232-00-00

12-20-1968

Operator's Full Name Zenith Drilling Corporation, Inc.

Complete Address: 300 West Douglas Wichita, Kansas

Lease Name Wetherill Well No. 1

Location NW NW SE Sec. 32 Twp. 10 Rge. 16 (E) (W) XX

County Rooks Total Depth 3660'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 6:30P Day 17 Month 12 Year 1968

The Above well was plugged as follows:

Total Depth 3660' 8 5/8 csg set at 157' cwc 90 sc.

4 1/2 csg set at 3615' cw 150 sk. cmt.

4 1/2 csg PBTD 3582' and perf. (3330-42)

Filled 4 1/2 csg with sand (3582-3300) and dumped 4 sc cmt. W/dump bailer. (3260-3300)

Cutoff and recov. 2840' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 25 sc gel W/5 sc hulls, plug and 150 sc 50-50

poz cement W/6% total gel. Max pres

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

12/23/68

INV. NO.

9074-U

Signed:

Geo F. Messing
Well Plugging Supervisor