

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

REC'D
STATE CORPORATION COMMISSION
FEB 28 1977
02-28-1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,684-0000 (of this well)

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Center, Wichita, Kansas

Lease Name Wetherill Well No. 1

Location 760° FSL & 330° FEL 230' S C NE SE SE Sec. 32 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3675'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10 A Day 26 Month 2 Year 1977

The above well was plugged as follows:

RTD 3675' 8 5/8 csg set 245' cwc 150 sx. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 2-28-77

INV. NO. 4708 W