

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5/12/78
MAY 12 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 19371 - 00 - 01 (for this well)

Operator's Full Name Cities Service Co.

Complete Address 700 Sutton Place, 209 East William, Wichita, Kansas 67202

Lease Name Kruse Unit Well No. 205W

Location SW SW SE Sec. 2 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3856'

Abandoned Oil Well Gas Well Input Well X ^{KCC} _{ZAP} SWD Well ~~XX~~ D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Sun Cementing Co.

Address License No.

Operation Completed: Hour 11 A Day 11 Month 5 Year 1978

The above well was plugged as follows:

Total Depth 3856' 8 5/8 csg set 2415' cwc 150 sk. cem.

5 1/2 csg set 3436' cw 200 sk. cem.

5 1/2 csg 2 stage col. at 1107' cwc 275 sk.

Perf. (3048'-3129') squeezed top of cem. 3000'. No pipe recovered.

Set 5 1/2" rubber plug at 615' -displaced 35 sk comm. cem. thru ~~bg.~~ (615'-335')

Set cementing plug at 90' filled to subface with 15 sk cem. (90' - 0)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben Massey
Well Plugging Supervisor

DATE 5-12-78

INV. NO. 7298-C