

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
3/29/68
MAR 29 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 553 Russell, Kansas 67665

Lease Name Kruse ^{KCC} ^{ZAP} Unit Formerly (Erway #1) Well No. 101 W

Location C N/2 NW SW Sec. 2 Twp. 10 Rge. 16 (E) (W) X

County Rooks Total Depth 3495

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 1 P Day 27 Month 3 Year 1968

The Above well was plugged as follows:

Total Depth 3495' 8 5/8 csg set at 137' cwc 100 sc.

5 1/2 csg set at 3467' cw 150 sc.

5 1/2 csg PBTD 3156' with top perf. at 3142'

5 1/2 csg squeezed (cedar-hills) at 738' W/220 sc cement.

No pipe recov.

Pumped down annulus (8 5/8-5 1/2) with 20 sc cement.

Squeezed thru 5 1/2 plug container with 4 sc hulls, 35 sc gel & water, 1 sc hulls,

plug and 90 sc cement. Max. pres. 1350 lbs. SI pres. 350 lbs. Circ pres 800-900 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. F. Massey
Well Plugging Supervisor

DATE 3/29/68
INV. NO. 17495-W