

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 22-16 County: Rooks

Location: CSL SE NW Sec. 2 Twp. 10 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3355

I have this date completed supervision of plugging of:

Lease Name: Hedge Well No. 1

Operator's Full Name: Broadview Oil Co

Complete Address: c/o Southwest Casing Pulling Co Box 364 Great Bend, Kans

Plugging Contractor: Southwest Casing Pulling Co

Address: Box 364 Great Bend, Kans License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 15 Month 3 Year 59

The above well was plugged as follows:

8 5/8" at 86' circulated with cement- 5 1/2" 3355' with 125 sax cement.

P.B. to 3124', perforated ~~383~~ 3083'.

Filled with sand to 3070', set 4 sax cement with dump bailer, pulled

2478' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550',

(26 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud

to 150', displaced 20 sax cement through 5 1/2" at 150', heavy mud to 35',

set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Cementing Co.

Received
3/18/59

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 2 T 10 R 16 W
BOOK PAGE 22 LINE 16