

KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION 8/18/51 AUG 8 1961 CONSERVATION DIVISION Wichita, Kansas

TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

File No. _____ County: _____ Rooks Location: CS 1/2 SW NW Sec. 2 Twp. 10 Rge. (E) (W) 16 Name of Field: _____ Total Depth: 3310 3315 KCC ZAY

I have this date completed supervision of plugging of:

Lease Name: Kruse Well No. 1

Operator's Full Name: R. B. Schmidt & Knight Casing Pulling Co

Complete Address: Knight Casing Pulling Co Box 304 Chase, Kansas

Plugging Contractor: Knight Casing Pulling Co

Address: same License No. 436

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 1 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 225' circulated with cement - 5 1/2" 3310' with 75 sax cement - PB to 3240' - perforated 3100'.

Plugs and sand to 3080', set 4 sax cement with dump bailer, pulled 770' 5 1/2" to 420', circulated hole with heavy mud through 5 1/2" (gel mud), displaced 20 sax cement through 5 1/2" at 420', heavy mud to 170', displaced 20 sax cement through 5 1/2" at 170', heavy mud to 25', set plug and filled to bottom cellar with cement.

Mudding and cementing by Knight Casing Pulling pump truck.

Signed: [Signature] Conservation Division Agent

Reviewed: [Signature] Field Supervisor

Remarks:

INVOICED DATE 8/18/61 INV. NO. 3592-W