

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-163-22,048-00-00

LEASE NAME Nelson

WELL NUMBER A-1

SPOT LOCATION NW SE NE

SEC. 28 TWP. 10 RGE. 16(E) OR (W)

COUNTY Rooks

DATE WELL COMPLETED 7-10-83

PLUGGING COMMENCED 7-10-83

PLUGGING COMPLETED 7-10-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Raymond Oil Company, Inc.

One Main Place, Suite 900

ADDRESS Wichita, KS 67202

PHONE #(316) 267-4214 OPERATORS LICENSE NO. 5046

CHARACTER OF WELL D & A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dale Balthazor

Is ACC-1 FILED? to be filed by operator IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3710'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom Plug: @ 3700' w/25 sacks 50/50 pozmix, 6% gel 3% cc. thru drill pipe

Next Plug: @ 1330' w/25 " " " " " " " " " "

Next Plug: @ 810' w/100 " " " " " " " " " "

Next Plug: @ 260' w/40 " " " " " " " " " "

Top Plug: @ 40' w/ Hulls plug and 10 sacks cement 10 sacks cement in Rat Hole

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Lobo Drilling LICENSE No. _____
ADDRESS P.O. Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, SS.

Ervin Neighbors (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) Ervin Neighbors
(ADDRESS) Box 877 Great Bend, KS 67530


SUBSCRIBED AND SWORN TO BEFORE ME THIS 20 DAY OF July, 1983

Dorothy M Hague
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

AUG 03 1983
08-03-1983
Wichita, Kansas

FORM CP-4
REVISED 06-83



MY COMMISSION EXPIRES: 4-29-86

15-163-22048-00-00

DRILLERS' WELL LOG

DATE COMMENCED: July 2, 1983
DATE COMPLETED: July 10, 1983

Raymond Oil Co., Inc.
NELSON A-1
NW SE NE
Sec. 28, T10S, R16W
Rooks County, Ks.

ELEVATION: 2116' K.B.

0 - 1310' Surface Soil, Red Bed, Shale
1310 - 1344' Anhydrite
1344 - 3314' Lime & Shale
3314 - 3559' Lime
3559 - 3701' Shale, Lime, Chert, Sand
3701 - 3710' Dolomite
3710' RTD

FORMATION DATA

Anhydrite 1310'
Topeka 3033'
King Hill 3139'
Queen Hill 3198'
Heebner 3269'
Toronto 3291'
Lansing 3314'
Base K.C. 3559'
Marmaton 3569'
Conglomerate 3649'
Cong. Chert 3659'
Arbuckle 3701'
RTD 3710'

Surface Pipe: Set new 8-5/8", 20#
pipe @ 249' w/150 sacks 60/40
pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 20 day of July 1983.

My Comm. Expires:

4-29-86

Barbara M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 01 1983
08-03-1983