

15-163-00035-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Rooks County. Sec. 28 Twp. 10S Rge. (E) 16W

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW NW SW

Lease Owner. C. E. Ash et al

Lease Name. O. F. Krueger Well No. A1

Office Address. 309 Petroleum Building; Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed. 9-25 19. 46

Application for plugging filed. 9-25 19. 46

Application for plugging approved. 9-25 19. 46

Plugging commenced. 9-25 19. 46

Plugging completed. 9-26 19. 46

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production. 19.

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr

Producing formation. Arbuckle Depth to top. 3659 Bottom. 3711 Total Depth of Well. 3711 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	3659	3711	8-5/8	201	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with 10.7# rotary mud to 200' Wood plug set at 200'
15' of chat, cemented with 15 sacks cement. Muded to 40'
Set wood plug at 40' 5' chat Cemented with 10 sacks
cement. Filled to surface with dirt.

PLUGGING
FILE 28 10-16W
BOOK PAGE 7-5 LINE 15

STATE CORPORATION COMMISSION
OCT 3 - 1946
10-03-1946

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C. E. Ash
Address. 309 Petroleum Building; Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, C. E. Ash, ~~XXXXXXXXXXXXXX~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Ash

309 Petroleum Bldg.; Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of October, 1946.

My commission expires 9/10/1947

John E. Johnson
Notary Public.



15-163 - 00035-00-00

C E ASH et al

O F Krueger A 1

SW NW SW Sec. 28-10-16W
Rooks, County, Kansas

Comm. Rig Up : 9-6-1946	Elevation :
Comm. Drlg. : 9-8-1946	Initial Prod : D & A
Completed : 9-26-1946	Contractor : C E Ash
Total Depth : 3711'	Tools : Rotary

CASING RECORD


<u>Run</u>	<u>Pulled</u>	<u>Left In</u>
201' - 8-5/8" Surface		201' - 8-5/8" Surface

<u>STRATA</u>	<u>DEPTH</u>
---------------	--------------

Gravel and shale	30
Black shale	395
Sand and shale	585
Sand	685
Sand and shells	760
Sand	845
Sandy shale	900
Red rock and shale	935
Shale and shells	970
Red rock and shale	1195
Anhydrate lime	1229
Shale and shells	1265
Red rock and shells	1530
Shale and shells	1640
Salt	1750
Shale and shells	1835
Lime and shale	1940
Lime	1990
Lime and shale	2145
Lime	2470
Shale	2485
Lime	2545
Shale and shells	3040
Lime	3071
Shale and lime	3093
Lime	3502
Shale and lime	3539
Cherty conglomerate	3632
Conglomerate and lime	3667
Lime	3711
Total Depth	3711

FORMATION TOPS - Rotary Bushings

Lansing	3193
Conglomerate	3494
Simpson Dolemite	3625
Arbuckle	3659



I hereby certify that the above is the true and correct log of said well as reflected by the daily drilling reports.

28 10-16W
75-15-

Beash

Subscribed in my presence and sworn to before me this 2nd day of October, 1946.

Jan E. Johnson
Notary Public in and for
Sedgwick County, Kansas

My Commission expires September 10, 1947

