

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 525'; set plug, cemented with 15 sacks cement
 Filled hole with heavy drilling mud to 165'; set plug, cemented with 1/2 sack hulls and
 15 sacks cement
 Filled hole with heavy drilling mud to 40'; set plug, cemented with 1/2 sack hulls and
 10 sacks cement to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1959
02-11-1959
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gartner

(Address)

SUBSCRIBED AND SWORN to before me this 9th. day of February, 19 59

My commission expires May 17, 1962

Notary Public.

PLUGGING

FILE SEC. 28 T. 10 R. 16W
BOOK PAGE 9 LINE 7

15-163-00774-00-00

DRILLER'S WELL LOG

Davis Bros.-Transit Corporation - Nelson "G" # 1 well located in
260'W C NW SE Section 28-10S-16W,
Rooks County, Kansas

Commenced: December 12, 1958
Completed: December 23, 1958
Elevation: 2078' KB

Casing 8 5/8" @ 183'
Cemented w/130 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Summary of Formation</u>	
Post rock	0	45	Topeka	2998'
Shale and shells	45	100	Heebner	3234'
Sand and gravel	100	150	Toronto	3255'
Shale	150	470	Lansing	3278'
Sand	470	495	Conglomerate	3618'
Shale	495	550	Arbuckle	3682'
Sand and shale streaks	550	725		
Shale and sand streaks	725	1000		
Red bed sand and shale	1000	1240		
Shale	1240	1243		
Anhydrite	1243	1280		
Shale and shells	1280	1595		
Shale	1595	1830		
Lime and shale	1830	2695		
Shale and lime	2695	2870		
Lime and shale	2870	3070		
Lime	3070	3540		
Lime and shale	3540	3625		
Chert	3625	3650		
Lime	3650	3674		
Lime and shale	3674	3682		
Lime	3682	3712 TD		

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me
this 9th day of February, 1959.
My Commission expires May 17, 1962.

TRANSIT CORPORATION

BY Paul E. Gathers

Mildred Dean
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
02-11-1959
FEB 11 1959
CON
DIVISION
Tulsa, Kansas

PLUGGING

FILE SEC 28 T 10 R 16W
BOOK PAGE 9 LINE 7