

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,097-00-00

LEASE NAME George

WELL NUMBER 4

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 31 TWP. 10SRGE. 16W (X or W)

COUNTY Rooks

Date Well Completed N/A

Plugging Commenced 2/24/94

Plugging Completed 2/24/94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS P.O. Box 641

PHONE# (913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/23/94 (date)

by Don Butcher, Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well loc. attached? Yes

Producing Formation Topeka, L-K.C. & Conglomerate Depth to Top 2886 Bottom 3468 T.D. 3550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		200	0	8-5/8	200	0
N/A		3543	0	4-1/2	3543	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Entered hole, could not get past 1000' pulled tubing to 960', circulated 100 sks common cement down tubing and back to surface. Closed in 4-1/2" casing, pumped another 100sks common and 30 sks 65/35. Tied on to 8-5/8" casing and pumped 150 sks 65/35 cement, (shut in pressure 100#). Tie back onto 4-1/2" casing and pump additional 25 sks 65/35 cement (shut in pressure 400#).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P.O. Box 31, Russell, KS 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige (Employee of Operator) or (Representative of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kenneth Vehige
Kenneth Vehige, President

(Address) P.O. Box 641



SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 94

Verda M. Brin
Notary Public Verda M. Brin

My Commission Expires: 7-18-95

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1994
03-28-1994

CONSERVATION DIVISION
Wichita, Kansas