

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

15-163-21691-00-00

COUNTY Rooks SEC. 31 TWP. 10S RGE. 16W E/W
 Location as in quarters or footage from lines:
N/2 NW SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Montgomery Exploration, Inc.
 Lease Name Whisman A-2 Well No. _____
 Office Address P.O. Box 1114 Hays, Kansas 67601
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 5-12-83
 Plugging completed 5-19-83
 Reason for abandonment of well or producing formation _____

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation _____ Depth to top _____ bottom T.D. 3602'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	211'	none
				4-1/2"	3597'	2493'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped bottom with 50 sacks 50/50 pos, 6% gel, 2 hulls and 4-1/2" plug to 2850'.
 Shot casing @2700' and 2500', layed down 61 joints (2493') of 4-1/2" casing.
 Plugged well with 4 hulls, 5 gel, 25 cement, 8 gel, 70 cement, 5 gel, 8-5/8" plug
 and 70 cement, 50/50 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Keiso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Keiso
Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd. day of May, 19 83

My Commission expires:



Irene Hoover
 RECEIVED Notary Public.
 STATE CORPORATION COMMISSION
05-24-1983
MAY 24 1983