

15-143-20314-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

Rooks County, Sec. 32 Twp. 10 Rge. (E) 16 (W)

Location as "NE/CNWxSWx" or footage from lines C S/2 SW SW

Lease Owner Beacon Resources Corp.

Lease Name Wetherill Well No. 1

Office Address 1000 Century Plaza - Wichita Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 6-13 19 70

Application for plugging filed 6-13 19 70

Application for plugging approved 6-13 19 70

Plugging commenced 4:15 PM 6-13 19 70

Plugging completed 5:30 PM 6-13 19 70

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3200 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	0	0 XXX	215	8 5/8"	215	0
RECEIVED STATE CORPORATION COMMISSION JUN 16 1970 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug hole 70 sx @ 600' w/20 sx @ 210' & 40' w/10 sx
2 sx in rat hole by Lwo Massey & Sun cementing

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B Drilling, Inc.

Address 720 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Bill Lahar (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar

720 Union Center - Wichita, Kansas


(Address)

Subscribed and sworn to before me this 15th day of June, 19 70

Alma A. Neises

Notary Public.

May 31, 1974



B & B DRILLING, INC.
207 Petroleum Building
Wichita, Kansas 67202

June 15, 1970

15-143-20314-00-00

DRILLERS LOG

Re: Wetherill #1
C S/2 SW SW Section 32-10S-16W
Rooks County, Kansas

OPERATOR: Beacon Resources Corp.
CONTRACTOR: B & B Drilling, Inc
COMMENCED: June 7, 1970
COMPLETED: June 13, 1970
TOTAL DEPTH: 3200'

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1970

CONSERVATION DIVISION
Wichita, Kansas

06-16-1970

0	225	Surface		
225	288	Shale		
288	1205	Shale & Sand		
1205	1210	Anhydrite		
1210	1241	Anhydrite		
1241	1565	Shale		
1565	1940	Shale & Lime		
1940	2151	Shale & Lime		
2151	2301	Lime		
2301	2434	Lime		
2434	2780	Shale		
2780	2985	Lime & Shale		
2985	3036	Lime		
3134	3200	Lime		
3200		Total Depth	Logged	D & A

We cerryify the above and foregoing to be true
and correct copy of the log on the #1 Wetherill
located in Rooks County, Kansas

Bill Fisher President

Alfred A. Neises Notary Public

Subscribed and sworn to before me this 15th day of
June, 1970, My commission expires May 31, 1974

