

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-19374-00-00

API NUMBER 15

LEASE NAME Kruse

WELL NUMBER 206-S

1100 Ft. from S Section Line

1150 Ft. from E Section Line

SEC. 16 TWP 10S RGE. 16W (for (W))

COUNTY Denver

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-13-93

Plugging Completed 9-13-93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Gold Petroleum Inc.

ADDRESS 3917 So. Peach Way Denver, Co. 80237

PHONE # 303 758 3591 OPERATORS LICENSE NO. 31233

Character of Well SW

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-11-93 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Dakota Depth to Top 765' Bottom 838' T.D. 838'

Cement on Bottom

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota	Sand to water	765'	838'	7"	738'	None
					7" casing	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Ran bit and scraper to 838'. Ran 2" tubing to 810' pumped 100 sacks 65/35 poz 6% gel down tubing cement circulated to surface. Pulled tubing tied onto 7" casing squeezed with 125 sacks cement 200 lbs. hulls at 400 psi. and a shut in pressure of 200 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Randy's Well Service License No. #511 58 07 50

Address Rout 1 Codell, Kn.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gold Petroleum Inc.

STATE OF Colorado COUNTY Denver, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3917 S. Peach Way Denver, CO 80230

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 1993

[Signature] Notary Public

My Commission Expires: My Commission Expires Feb. 22, 1997

