

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks

County. Sec. 2 Twp. 10S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE-NE-NE

Lease Owner L.D. Sargent

Lease Name Pfortmiller Well No. #1

Office Address 2548 Mc Bride Great Bend, Kansas.

Character of Well (completed as Oil, Gas or Dry/Hole) Dry hole

Date well completed 3-2 19 51

Application for plugging filed 3-2 19 51

Application for plugging approved 3-2 19 51

Plugging commenced 3-2 19 51

Plugging completed 3-2 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Pfortmiller #1
Sec. 2-10S-16W
Rooks County, Ks.

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3609 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------------------|---------|------|-------|--------|--------|------------|
| Soll, postrock, shale | | 0 | 155' | 8 5/8" | 155' | none |
| Kansas City | | 3170 | 3498' | Dry | | |
| Arbuckle | | 3559 | 3609 | Dry | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Stirred pits with, filled with heavy mud to 150'. Placed bottom wood plug at 150' ran 15 sacks of well mixed cement through the drill pipe on same. Filled hole with heavy mud to 40'. Placed top wood plug and 1/2 sack hulls at 40', and ran 10 sacks cement through drill pipe filling hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
3/6/51
MAR 6 1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Strain Drilling Company
Address Box 188 Hays, Kansas.

STATE OF Kansas, COUNTY OF Ellis, ss.
T.C. Strain

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.C. Strain

Box 188 Hays, Kansas.
(Address)

My commission expires before me this 5th day of March, 1951

LeRoy R. Power
Notary Public.



PLUGGING
FILE SEC 2 T 10R 16W
MAR 65 1951

COMPANY: L.D. Sargent et al

NE NE NE Sec. 2, Twp. 10S
Rgs. 16W,
Rooks County, Kansas.

LEASE: Pfortmiller #1

ELEVATION: 2011 D.F.
NOTE: All meas. rotary bushings.

| | |
|------|----------------------|
| 0 | 85 Soil |
| 85 | 100 Shale & shells |
| 100 | 250 Shale |
| 250 | 795 Shale & shells |
| 795 | 820 Sand |
| 820 | 865 Shale |
| 865 | 1065 Red Bed & sand |
| 1065 | 1180 Red bed & shale |
| 1180 | 1230 Anhydrite |
| 1230 | 1325 Red bed & shale |
| 1325 | 1740 Shale & shells |
| 1740 | 1930 Shale & lime |
| 1930 | 2085 Shale & lime |
| 2085 | 2155 Lime |
| 2155 | 2265 Lime |
| 2265 | 2405 Lime |
| 2405 | 2490 Lime & shale |
| 2490 | 2690 Shale & shells |
| 2690 | 2900 Shale & shells |
| 2900 | 2985 Shale & shells |
| 2985 | 3055 Lime & shale |
| 3055 | 3110 Lime & shale |
| 3110 | 3180 Lime |
| 3180 | 3250 Lime |
| 3250 | 3292 Lime |
| 3292 | 3340 Lime |
| 3340 | 3410 Lime |
| 3410 | 3475 Lime |
| 3475 | 3498 Lime |
| 3498 | 3530 Conglomerate |
| 3530 | 3559 Conglomerate |
| 3559 | 3609 Arbuckle |

COMMENCED: 2-18-51
COMPLETED: 3-2-51

RECORD CASING:

8 5/8" Surface casing set at
155' 115 Sacks cement by
Globe Cementing Company.

No Drill Stems or electric logs
taken.

TOPS:

| | | | |
|-------------|------|-------------|------|
| Anhydrite | 1180 | Arbuckle | 3559 |
| Heebner | 3124 | Total Depth | 3609 |
| Kansas City | 3170 | | |

STATE OF KANSAS)
)SS
COUNTY OF ELLIS)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Pfortmiller # 1, located NE NE NE Sec. 2, Twp. 10S Rgs. 16W, Rooks County, Kansas.

CONTRACTOR: STRAIN DRILLING CO.

By: T.C. Strain
T.C. Strain

Subscribed and sworn to before me this 5th day of March, 1951

My Commission expires March 1, 1954, 19

Lesoy R. Power
NOTARY PUBLIC.

PLUGGING
FILE SEC 2 T 10 R 16W
BOX 6 S 10 E 19