

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-21,342-00-00

LEASE NAME Becker

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

990 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR McGinness Oil Company

SEC. 2 TWP. 10S RGE. 16 ~~XXXX~~ (W)

ADDRESS 1026 Union Center Bldg., Wichita, KS

COUNTY Rooks

PHONE# (316) 267-6065 OPERATORS LICENSE NO. 5255

Date Well Completed 08-07-81

Character of Well Oil

Plugging Commenced 04-02-86

(Oil, Gas, ~~DLA, SWD, Input, Water Supply Well~~)

Plugging Completed 04-02-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6 - Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Toronto Depth to Top 3093' Bottom 3113' RTD 3380'
Lansing Depth to Top 3115' Bottom 3309' T.D. LTD 3340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	285'	None
				4 1/2"	3372'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf 2 shots in middle of Anhydrite at 1155'-1156' & 2 shots at 290'-294'.
Cemented w/100 sx of 60-40 Poz (10% gel) w/2 sx hulls, cemented down backside,
Max Press #200, SIP #50. Cemented down 4 1/2" casing w/200 sx 60-40 Poz (10%
gel) w/10 sx hulls, Max Press #300, SIP #100.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address Box 342, Plainville, Kansas 67663

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

I, Douglas H. McGinness ~~State Corporation Commission Operator~~ (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. STATE CORPORATION COMMISSION help me God.

(Signature) Douglas H. McGinness

(Address) 1026 Union Center Building
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 86

De Ann Renee Konkell
Notary Public

My Commission Expires: April 8, 1989

