

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-21083-00-00

LEASE NAME Becker

WELL NUMBER 2

3960 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 2 TWP. 10S RGE. 16 (E) or (W)

COUNTY Rooks

Date Well Completed 8/28/80

Plugging Commenced 3/1/91

Plugging Completed 3/5/91

Amended

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Leben Oil Corporation

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6566

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/1/91 (date)

by Gibb Scheck (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -
 Congl.

Producing Formation Toronto/LKC/Marm./ Depth to Top 3070 Bottom 3414 T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

4/29/91
APR 29 1991

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	Oil	3070	73	8 5/8	287	None
LKC	Oil	3092	3277	4 1/2	3499	1625.40
Marmaton	Oil	3360	64			
Conglomerate	Oil	3402	14			

CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Bottom: 4 sxs cmt + sand. Top: Spotted 50 sxs 60/40 w/8% gel @ 1000', @ 800', @ 600', @ 400' and circulated 75 sxs from 200' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Leben Oil Corporation

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 91

Judith E. Jurnell
 Notary Public

My Commission Expires: 3-29-92



WELL LOG

OPERATOR: Leben Oil Corporation

WELL NAME: Becker #2 LOCATION: 2-10S-16W

COUNTY: Rooks STATE: Kansas

WELL COMMENCED: July 14, 1980 WELL COMPLETED: July 26, 1980

ELEVATION: 1951' K. B. TOTAL DEPTH: 3500'

PRODUCTION: Oil RIG NO: #1

CASING - 8-5/8": 287.16' of used 28# cemented with 150 sxs common 3% cc 2% rel
Cement Circ
4 1/2" ~~XXXXXX~~: 3498.78 of new 10 1/2# cemented with 150 sxs 60/40 poz with 10%

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	167'			
167'	295'	surface shale-blue	295' - 1/2 degree	
295'	840'	sand and shale		
840'	1120'	shale and sand		
1120'	1159'	Anhydrite		
1159'	1340'	shale	1692' - 3/4 degree	
1340'	1625'	shale		
1625'	1830'	shale and lime		
1830'	2010'	shale		
2010'	2299'	shale		
2299'	2473'	lime and shale		
2473'	2655'	shale and lime		
2655'	2844'	shale and lime		
2844'	2925'	lime and shale		
2925'	2956'	lime and shale		
2956'	3053'	lime and shale	2956' - 3/4 degree	
3053'	3153'	lime and shale		
3153'	3256'	lime and shale		
3256'	3357'	lime and shale		
3357'	3423'	lime and shale		
3423'	3455'	lime and shale		
3455'	3455'			
3455'	3460'			
3460'	3485'	lime and shale		
3485'	3500'	lime and shale		
3500'	RTD			

RECEIVED
STATE CONSERVATION DIVISION

JUL 5 1980

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.

By Roger J. Lomas

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 5th day of Aug, 1980.

Connie Jo Austin
NOTARY PUBLIC

CONNIE JO AUSTIN
STATE NOTARY PUBLIC
ROOKS COUNTY, KS.
KANSAS My Auth. Exp. 4-26-83