


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 3 Twp. 10S Rge. 16 ~~W~~ W
Location as "NE/CNW/SW" or footage from lines SE NE NW
Lease Owner Transit Corporation and Davis Bros.
Lease Name Welling "B" Well No. 1
Office Address 1516 Liberty Bank Building, Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed May 23, 19 58
Application for plugging filed May 23, 19 58
Application for plugging approved May 23, 19 58
Plugging commenced May 23, 19 58
Plugging completed May 23, 19 58
Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Box 326 Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	186	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 450', set plug, cemented with 20 sacks of cement,
Filled hole with heavy drilling mud to 180', set plug, cemented with 15 sacks of cement.
Filled hole with heavy drilling mud to 40', cemented with 10 sacks of cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
6/14/58
JUN 14 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gathers
(Address) _____

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1958

Medrel Iron
Notary Public.



PLUGGING
FILE SEC 3 T. 10 R. 16W
BOOK. PAGE 105 LINE 13

15-163-00751-00-00

DRILLER'S WELL LOG

Transit Corporation - Welling "B" # 1 located NE SE NW
 Sec. 3-10S-16W, Rooks County, Kansas

Commenced: May 12, 1958
 Completed: May 23, 1958
 Elevation: 2032 KB

Casing 8 5/8" @ 186'
 Cemented 135 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Post rock	0	38
Shale and shells	38	125
Sand	125	165
Shale	165	186
Shale and shells	186	696
Sand	696	821
Pyrite and shale	821	850
Shale and shells	850	1015
Red bed	1015	1190
Anhydrite	1190	1228
Red bed and shale	1228	1400
Shale	1400	1780
Lime and shale	1780	2010
Lime and shale streaks	2010	2100
Lime and shale	2100	2300
Shale and lime streaks	2300	2400
Shale and lime	2400	2490
Lime and shale	2490	2505
Shale and lime	2505	2550
Shale	2550	2760
Shale and lime streaks	2760	2900
Lime and shale	2900	3276
Lime	3276	3510
Conglomerate	3510	3605 TD

Summary of Formation

Anhydrite	1190'
Base Anhydrite	1223'
Topeka	2899'
Heebner	3132'
Toronto	3151'
Lansing KC	3175'
Base KC	3408'
Conglomerate	3505'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

TRANSIT CORPORATION

By Paul E. Gathers
 Paul E. Gathers

Subscribed and sworn to before me
 this 9th day of June, 1958.

My Commission expires May 17, 1962.

Mildred J. ...
 Notary Public



PLUGGING
 FILE SEC. 3 T. 10 R. 16W
 BOOK PAGE 105 LINE 13