

15-065-21736-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY GRAHAM SEC. 32 TWP. 9 RGE. 22 E/W
Location as in quarters or footage from lines:

		32	

Lease Owner EAGLE EXPLORATION, INC.
 Lease Name WEST Weller West KCC 2#1 Well No. 1
 Office Address 107 N. MARKET, SUITE 300 WICHITA, KS. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
 Date Well Completed _____
 Application for plugging filed 12-28-82
 Plugging commenced 12-19-82
 Plugging completed 12-19-82
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

NO RECOVERABLE HYDROCARBONS
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MARION SCHMIDT
 Producing formation NONE Depth to top _____ bottom _____ T.D. 3868

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	246'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. CEMENT USED 50:50 POZ 3% CACL 6% GEL

<u>3868' to 1890'</u>	<u>DRILLING MUD</u>
<u>1890' to 1840'</u>	<u>20 SAX</u>
<u>1840' to 1140'</u>	<u>DRILLING MUD</u>
<u>1140' to 1118'</u>	<u>11 SAX</u>
<u>1118' to 270'</u>	<u>DRILLING MUD</u>
<u>270' to 158'</u>	<u>40 SAX</u>
<u>158' to 40'</u>	<u>DRILLING MUD</u>
<u>40' to SURFACE</u>	<u>WOODEN PLUG & 10 SAX</u>
<u>10 SAX MOUSE HOLE,</u>	<u>10 SAX RAT HOLE</u>

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MACDONALD DRILLING INC. (DRILLING CONTRACTOR)


STATE OF KANSAS COUNTY OF GRAHAM, ss.

CARL DURR (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Durr

(Address) _____

SUBSCRIBED AND SWORN TO this 30th day of December, 19 82



Jeff P. Vogan
Notary Public

My Commission expires: _____