

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 32 Twp. 9 Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE

Lease Owner Tulsa Supply Company

Lease Name Sturgeon Well No. 1

Office Address Box 924, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 4-14-66 19

Plugging completed 4-16-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Nichols

Producing formation Depth to top Bottom Total Depth of Well 3854 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	203'	None
				5-1/2"	3854'	1317'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3835', sanded hole to 3770' and dumped 5 sacks of cement @ 3770' with dump bailer. Pulled 5 1/2" casing to 590' and circulated with 13 sacks of gel mud. Pulled 5 1/2" casing to 430' and pumped in 7 sacks of gel mud. Pulled 5 1/2" casing to 366' and pumped in 20 sacks of cement. Pulled 5 1/2" casing to 206' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, bailed hole to 35', set rock bridge and capped well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
5/2/66  
MAY 2 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1966

My commission expires May 20, 1968 Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1966

## STURGEON #1

LOCATION: NE NW SE - Sec. 32,  
Twp. 9.S, Rge. 22.W,  
Graham County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.  
712 Union Center  
Wichita, Kansas

SURFACE CASING: 203' 8 5/8" cemented with 135  
sacks cement, 200# Calcium  
Chloride, 1% gel.

OIL STRING: 3834' 5 1/2" cemented with  
100 sacks cement, 2% gel.

ELEVATION: 2355' K. B.  
2352' D. F.  
2350' G. L.

COMMENCED: August 2, 1956

COMPLETED: August 13, 1956

## WELL LOG

0 - 130	Surface Clay and Sand
130 - 715	Shale
715 - 1705	Shale and Sand
1705 - 1872	Shale and Shells
1872 - 1910	Anhydrite
1910 - 2195	Shale and Shells
2195 - 2715	Shale and Lime
2715 - 2795	Lime
2795 - 3285	Shale and Lime
3285 - 3835	Lime
3835	Rotary Total Depth

The undersigned, J. W. Owen, an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Sturgeon as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

*J. W. Owen*  
J. W. Owen, Sec.-Treas.

Subscribed and sworn to  
before me this 15th day of  
August, 1956.

*Leta Helm*  
Leta Helm - Notary Public

My commission expires:  
August 25, 1956.