

15-065-01543-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NONE

LEASE NAME Sturgeon

WELL NUMBER 2

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 32 TWP. 9S RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 11-9-55

Plugging Commenced 10-13-92

Plugging Completed 10-13-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ROBERT R. PRICE OPERATING, INC.

ADDRESS P.O. Box 470442, Tulsa, OK 74147

PHONE# (918) 492-1694 OPERATORS LICENSE NO. 6273

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on letter dated 9-1-92. Telephone approval 10-1-92. (date)
by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? yes

Producing Formation Lansing-KC Depth to Top 3605' Bottom 3830' T.D. 3845'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing-KC	Oil	0'	234'	8 5/8"	234'	
		0'	3837'	5 1/2"	3837'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated Anhydrite at 1920' to 1921' with 3 holes. Pumped 100 sx. of 60-40 pozmix down 5 1/2" - 8 5/8" annulus. Pumped 300 sx. of 60-40 pozmix 10% gel and 6 sx. of hulls down casing. 400# maximum pressure. 200# standing pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Robert R. Price Operating, Inc. License No. 6273

Address P.O. Box 470442, Tulsa, OK 74147

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert R. Price Operating, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Robert R. Price

(~~Individual Operator~~) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well that are true and correct, so help me God.

(Signature) Robert R. Price, President

(Address) P.O. Box 470442, Tulsa, OK 74147

SUBSCRIBED AND SWORN TO before me this 22nd. day of October 1992 at Wichita, Kansas

Rachel Shamlin
Notary Public

My Commission Expires: February 26, 1994



15-065-01543-00-00

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
November 23, 1955

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: October 28, 1955
Drilling Completed: November 9, 1955

Sturgeon #2 NE/4 Sec. 32-
9S-22W, Graham County,
Kansas.

DRILLERS LOG

Surface Clay & Sand	0-40
Sand & Shale	40-236
Shale & Shells	236-790
Shale & Sand	790-810
Sand & Shale	810-1640
Red Bed & Shale	1640-1870
Red Bed	1870-1875
Anhydrite	1875-1915
Shale & Shells	1915-1995
Shale & Lime	1995-2170
Shale & Shells	2170-2350
Shale & Broken Lime	2350-2485
Shale & Lime	2485-2625
Lime	2625-2745
Lime & Shale	2745-2900
Shale & Lime	2900-3040
Lime & Shale	3040-3445
Lime	3445-3510
Lime & Shale	3510-3600
Lime	3600-3801
Lime & Shale	3801-3840
Lime	3840-3845 T.D.

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Sturgeon #2 NE/4 Section 32-9S-22W, Graham County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Borham
Notary Public

February 13, 1956
My Commission Expires

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1992

Wichita, Kansas