

15-015-00342-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Butler County, Sec. 3 Twp. 28 Rge. 3 (E)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SE

Lease Owner Mallonee Drilling Co. Inc.

Lease Name Young Well No. 1

Office Address 812 Central Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 19 19 52

Application for plugging filed June 19 19 52

Application for plugging approved June 19 19 52


Plugging commenced June 19 19 52

Plugging completed June 19 19 52

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Lawrence Matthews

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 180'  
Wood plug at 180' with 10 sacks of cement  
Mud to 15' - cemented top cap with 5 sacks

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Martin & Cash Drilling Co.  
Address 110 E. 5th, Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Clovis G. Cash (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Clovis G. Cash*  
110 E. 5th Ave., Augusta, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16 day of July, 19 52  
August 27, 1955  
My commission expires



Grace E. Johnson  
Notary Public.

23-8390-s 6-51-20M  
**PLUGGING**  
FILE SEC 3 T 2 R 36  
BOOK PAGE 28 LINE 23

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1952  
CONSERVATION DIVISION  
Wichita, Kansas

Well Log

15-015-00342-00-00

Company: Mallonee Drilling Co., Inc.

SE NE SE  
Sec. 3-28S-3E  
Butler County, Kansas

Farm: Young #1

Total Depth: 3116'

Commenced: 6/5/52

Completed: 6/19/52

Casing: 171' of 8 5/8" cem. w/ 120 sks.

\*\*\*\*\*

lime	0-75	sand	3033-3040
sandy lime w/ shale	75-135	sand & shale	3040-3059
gyp.	135-138	lime sandy	3059-3093
stickey shale	138-154	Arb. lime	3093-3116
lime	154-160		
lime	160-171	total depth	3116
lime sandy	171-280		
shale and lime	280-360		
red rock	360-370		
lime	370-380		
lime	380-415		
lime & shale	415-505		
shale & lime	505-620		
shale & lime	620-900		
shale & shells	900-990		
shale & lime	990-1115		
shale & shells	1115-1215		
shale & shells	1215-1235		
shale & lime	1235-1395		
shale & lime	1395-1420		
lime w/ shale strks	1420-1475		
shale & shells	1475-1545		
lime	1545-1590		
lime	1590-1630		
shale & lime	1630-1680		
lime & l. shale	1780-1729		
lime & l. shale	1729-1820		
sandy lime	1820-1890		
lime & shale	1890-1940		
lime	1940-2000		
shale & lime	2000-2043		
lime & shale	2043-2094		
shale & lime	2094-2205		
shale	2205-2295		
lime K. C.	2294-2340		
lime	2340-2422		
shale & lime	2422-2465		
lime	2465-2490		
shale & shells	2490-2530		
lime & shale	2530-2556		
lime & shale	2556-2633		
lime & shale	2633-2709		
shale & lime	2709-2730		
lime	2730-2746		
lime & shale	2746-2779		
Miss. lime	2779-2815		
lime	2815-2862		
lime	2862-2891		
lime	2891-2907		
lime	2907-2943		
lime	2943-2965		
shale & lime	2965-2977		
shale & lime	2977-3033		

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 24 1952  
CONSERVATION DIVISION  
Wichita, Kansas

The foregoing is hereby certified to be a true and correct copy of the rotary drilling log on the above designated well.

Subscribed and sworn to before me this 9th day of July 1952

Martin & Cash Drilling Company  
Partner

*Grace E. Johnson*  
NOTARY PUBLIC

**PLUGGING**  
FILE SEC 3 T 28 R 36  
BOOK PAGE 24 LINE 23