

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-015-22,645-00-00

LEASE NAME Pray B

WELL NUMBER #2

SPOT LOCATION SW NW SW

SEC. 6 TWP. 28 SRGE. 3 (E) DRILL

COUNTY Butler

Date Well Completed 12-9-84

Plugging Commenced 12-9-84

Plugging Completed 12-9-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Watson Petroleum, Inc.

ADDRESS 403 N. Hillcrest, Wichita, Kansas 67208

PHONE # (316) 682-7131 OPERATORS LICENSE NO. 5587

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #2

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 3160

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	212	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Spotted 35 sx cement @ 260' thru drill pipe.

Spotted 25 sx cement @ 60' thru drill pipe.

Spotted 10 sx cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 401 E. Douglas, Suite 500


Wichita, Ks. 67202

before me this 21st day of December, 1984

My Commission expires:



David F. Jamis
Notary Public



15-015-22645-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Watson Petroleum
 403 N. Hillcrest
 Wichita, Kansas 67208

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
 Wichita, Ks. 67202

Lease Name Pray B Well No. #2

Sec. 6 T. 28S R. 3E Spot SW NW SW

County Butler State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 212' with 90 sx, 3% cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3160

Drilling Commenced 12-3-84 Drilling Completed 12-9-84

Formation	From	To	Tops
Cellar	0	7	
Shale	7	400	
Shale, Lime	400	1329	
Lime, Shale	1329	1550	
Shale, Lime, Sand	1550	1784	
Shale, Lime	1784	1843	
Sand, Shale	1843	1916	
Shale	1916	2016	
Lime	2016	2062	
Lime, Shale	2062	2120	
Shale	2120	2187	
Lime	2187	2201	
Shale, Sand	2201	2275	
Shale	2275	2397	
Lime	2397	2571	
Lime, Shale	2571	2850	
Lime	2850	3009	
Lime, Shale	3009	3160	

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1984

CONSERVATION DIVISION
Wichita, Kansas