


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Butler County, Sec. 5 Twp. 28S Rge. 3 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NE NE
Lease Owner Gaty & Graham
Lease Name Graham "A" Well No. #3
Office Address 211 North Broadway
Character of Well (completed as Oil, Gas or Dry Hole) ~~dry hole~~ Oil ^{KCC} ~~2AP~~
Date well completed 19
Application for plugging filed 4/15/58 19
Application for plugging approved 4/15/58 19
Plugging commenced 4/24/58 19
Plugging completed 4/27/58 19
Reason for abandonment of well or producing formation ~~dry hole~~ Oil ^{KCC} ~~2AP~~

If a producing well is abandoned, date of last production September 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Lawrence W. Matthews
Producing formation Depth to top Bottom Total Depth of Well 3040 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil & Rock	0	0	60	10"	60*	None
		0	3078	7"	3078* 3076 ^{KCC} 2AP	2463.14*

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand to 2790' dumped 9 sx cement. Mudded hole up to 200' and set 10' rock bridge. Mixed and dumped 15 sx cement. Mudded hole to 20'. Set rock bridge and dumped 5 sx cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address P.O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
O.W. Woodland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaelis Drlg. Co.

(Signature) O.W. Woodland
211 North Broadway, Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 1st day of May, 19 58
Notary Public.

PLUGGING
FILE SEC 5 T 28 R 3 E
BOOK PAGE 93 LINE 29

RECEIVED
STATE CORPORATION COMMISSION
8/22/58
AUG 22 1958
CONSERVATION DIVISION
Wichita, Kansas

15-015-19811-00-00

COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - GATY & GRAHAM
Farm - Graham "A" No. 3

SEC. 5 T. 28 R. 3E
SW NE NE

Total Depth. 3048
Comm. 6-6-51 Comp. 6-21-51
Shot or Treated.
Contractor. Morrison Drlg. Co., Inc.
Issued. 8-11-51

County. Butler
KANSAS



Elevation. 1299
Production. -IPP 366 & 6% wtr.

Figures Indicate Bottom of Formations.

cement	60
shale	155
lime, shale	500
shale	564
shale, shells	725
sandy lime	830
shale	1060
lime, broken	1140
lime, shale brks	1300
shale	1350
lime, shale	1450
shale, lime brks.	1590
shale, lime brks.	1790
lime broken	1815
lime, shale	1900
shale	1938
lime, shale brks	1970
shale, lime brks	2007
lime	2020
lime, shale	2080
shale	2140
lime broken	2160
lime, shale brks	2315
lime, shale	2330
lime, K. C.	2523
shale	2615
shale, lime brks.	2720
lime, shale	2810
lime	2907
lime, shale	2929
lime	2976
lime, shale	3036
Top Simpson	3039
Free oil	3040
sand	3048
Total depth	

Scout tops:	
Kansas City	2330
Simpson	3039

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 5 T. 28 R. 3E
BOOK PAGE 43 LINE 29