

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-015-22,671-00-00

LEASE NAME Hooper C-J Hooper *KCC 2/4/91*

WELL NUMBER 3

4375 Ft. from S Section Line

1725 Ft. from E Section Line

SEC. 9 TWP. 28 RGE. 3 (E) or (W)

COUNTY Sedgwick

Date Well Completed 1/24/85

Plugging Commenced 7/12/91

Plugging Completed 7/19/91

LEASE OPERATOR BULLSEYE PETROLEUM, INC.

ADDRESS 15820 Plymouth, Box 781925, Wichita, Ks. 67278

PHONE# (316) 733-5280 OPERATORS LICENSE NO. 9913

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 20, 1991 (date)

by Don Thompson on 7/19/91, District #2 (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Simpson Depth to Top 3080 Bottom 3087 T.D. 3114

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface	water	0	200	8 5/8	214	None
Simpson	oil/water	3081 -	83	4 1/2	3120	2200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Built and place 90 ft. of sand/gravel from 3120 to 3030 topped with 5 sacks of cement. Shot and pull 2200 ft. of production casing. Ran 300 feet of tubing from surface to 300 feet, pumped plugging cement to surface. Cement holding and standing at surface, pulled tubing. Hole standing full of cement, shut down/plugged.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor McPherson Drilling Co. License No.

Address Rt. 2 - Box 168 D, Augusta, Kansas 67010

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bullseye Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

William Ash, Oper. Director (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William Ash

(Address) P.O. Box 781925, 15820 Plymouth Wichita, Ks. 9

SUBSCRIBED AND SWORN TO before me this 29 day of August, 1991

Midge Slupianek
Notary Public

My Commission Expires: _____

