

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-015-22587-00-012  
API NUMBER 15-22,587 (E24,859)

LEASE NAME HOOPER C-J C-J Hooper <sup>KCC</sup>

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3960 Ft. from S Section Line

1320 Ft. from E Section Line

LEASE OPERATOR BULLSEYE PETROLEUM, INC.

SEC. 9 TWP. 28 RGE. 3 (E) or (W)

ADDRESS 15820 Plymouth, Box 781925 Wichita, Ks. 67278 COUNTY Sedgwick Butler

PHONE# (316) 733-5280 OPERATORS LICENSE NO. 9913

Date Well Completed 9-11-84

Character of Well -SWD FOR AUB  
KCC

Plugging Commenced 3-23-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-6-90

The plugging proposal was approved on 3/22/90 and extension 6/18/90 (date)

by Shari Feist Albrecht (Don Thomson on location) (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Simpson Sand Depth to Top 3084 Bottom 3087 T.D. 3114

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Simpson Sand	water	3084	87	5 1/2"	3114	2040 <u>10/4/90</u>
				8 5/8"	216	none <u>OCT 4 1990</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. placed approx. 75 feet of sand in hole, 10' of gravel to cover 50' above perf. (3114' to 3035'), ran 5 sacks of cement on top. Drilling mud up to 2000 feet. Bailed well down to 300' from surface, built 40' rock bridge, bailed down well. Dumped 7 yards of cement slurry to surface. Hole standing full.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bail Down/Top Plug: Pluggers, Inc. - 3909  
Jonathan Oil License No. - 4231

Address Pluggers: 2316 Cypress, Wichita 67207 Jonathan: Box 1098, ElDorado 67042

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BULLSEYE PETROLEUM, INC.


STATE OF Kansas COUNTY OF Sedgwick, ss.

William Ash, Oper. Mgr. for Bullseye (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William Ash

(Address) 15820 Plymouth-Box 781925

Wichita, Kansas 67278



SUBSCRIBED AND SWORN TO before me this 4th day of October, 19 90

Midge Slupianek  
Notary Public

My Commission Expires: 6/3/91