

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County, Sec. 13 Twp. 28 Rge. 3 (E) *WV*

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE NW
 Lease Owner Welch & Olsson
 Lease Name Davenport Well No. 1
 Office Address 420 Fourth Nat'l. Bank Bldg., Wichita, Kans.
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 2-22-51 19
 Application for plugging filed 3-19-51 19
 Application for plugging approved 3-19-51 19
 Plugging commenced 3-27-51 19
 Plugging completed 3-27-51 19
 Reason for abandonment of well or producing formation Dry Hole
 If a producing well is abandoned, date of last production Dry Hole 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. L. Loman
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 2430 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

(100 ft. of 8 $\frac{1}{2}$ surface pipe cemented in)
 Mud to 2230'
 Set 3 sacks cement at 2230'
 Mud to 180'
 Set 10 sacks cement on 20' rock bridge at 160'
 Mud to surface
 Set 5 sacks cement cap.

RECEIVED
 STATE CORPORATION COMMISSION
 5124/51
 MAY 24 1951
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Welch & Olsson
 Address 420 Fourth Nat'l Bank Bldg.
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Welch (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. E. Welch*

(Address) 2222 Street, 1951

SUBSCRIBED AND SWORN to before me this 24th day of May, 1951
 June 12, 1951
 My commission expires.....

Notary Public.

PLUGGING
 FILE SEC-13 T-21 R-3E
 BOOK PAGE-67 LINE-36

LOCATION: DAVENPORT NO. 1
NW NE NW Sec. 13-28-3E
Butler County, Kansas

COMPANY: Welch & Olsson

CONTRACTOR: Eckland Drilling Co.

Casing:

Commenced: 1-24-51

Total Rotary Depth: 2416'

Completed: 2-22-51

Dry Hole

0	surface clay
50	shale
70	shale
115	shale lime shells
145	lime shale
260	lime shale
415	lime shale
745	shale lime shells
1095	shale shells
1130	shale shells
1190	lime shale
1280	shale
1335	lime shale
1505	lime shale
1645	lime shale
1800	lime shale
1845	lime
1935	lime shale
2050	lime shale
2080	lime
2135	lime shale
2215	shale
2238	lime K.C.
2257	lime (good odor)
2260	lime
2315	lime
2380	lime
2416	lime Total Depth

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1951
CONSERVATION

PLUGGING
FILE SEC 13 T 28 R 3E
BOOK PAGE 67 LINE 36

PLUGGING REPORT

DAVENPORT WELL # 1 - 13-28-3E
BUTLER COUNTY, KANSAS

3 Sacks Cement On Bottom.
Mud Up To 180 Ft.
10 Sacks Cement On 20 Ft. Rock Bridge At 160 ft.
Mud Up To 30 Ft.
5 Sacks Cement On 20 Ft. Of Rock & Filled To Surface.

#-27-51 Plugging Completed By C.V. Stewart & Co.
EL DORADO, KANSAS

APR 2 1951
OFFICE OF THE
COMMISSIONER OF
GEOL. & MINES
TOPEKA, KANSAS