

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Butler County, Sec. 13 Twp. 28S Rge. 3 (E) (W)

Location as "NE/CNW&SW" or footage from lines. C N/2 NW NW

Lease Owner John P. Gaty

Lease Name Kirkpatrick Well No. 2

Office Address 1601 East Douglas, Suite 201, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 6, 1963

Application for plugging filed February 6, 1963

Application for plugging approved February 6, 1963


Plugging commenced February 6, 1963

Plugging completed February 6, 1963

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation Depth to top Bottom Total Depth of Well 2319 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 170 feet. Set plug with 1/2 sack hulls and added 20 sacks cement. Filled with heavy mud to 25 feet. Set plug with 1/2 sack hulls and 8 sacks cement. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
2/18/63
FEB 18 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address Box 332, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X [Signature] Box 332, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15th day of February, 1963

My commission expires April 22, 1963 Betty Brandt Notary Public.



ROTARY DRILLERS' LOG

OPERATOR: JOHN P. GATY
4601 E. Douglas, Suite 204
Wichita, Kansas

DRILLING COMMENCED: February 3, 1963

CONTRACTOR: GRAVES DRILLING CO., INC.
Box 332
El Dorado, Kansas

DRILLING COMPLETED: February 6, 1963

CASING RECORD: 160' - 8-5/8" surface w/
125 sacks cement

LOCATION: Kirkpatrick No. 2
C N/2 NW NW
Section 13-28S-3E
Butler County, Kansas

0 -	3	Soil
3 -	45	Clay
45 -	48	Shale
48 -	52	Lime
52 -	65	Shale & clay
65 -	100	Red bed
100 -	112	Shale
112 -	160	Lime
160 -	800	Lime & shale
800 -	1186	Shale & lime
1186 -	2195	Lime & Shale
2195 -	2249	Shale
2249 -	2319	Lime
	2319	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1963
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Petty Brandt
Assistant Secretary

STATE OF KANSAS)
) SS
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 12th day of February, 1963.

My Commission Expires:
June 10, 1964

Opal Place
Opal Place Notary Public