

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.  
Address: P. O. Box 783188  
Phone: (316) 691-9500 Operator License #: 4767  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 08/17/2007 (Date)  
by: Marvin Mills (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing-Kansas City Depth to Top: 3581' Bottom: 3586' T.D. 3896'  
OH Arbuckle Depth to Top: 3884' Bottom: 3896' T.D. 3896'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-195-30238-00-00  
Lease Name: Deutscher "P"  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SE - NW  
1650 Feet from  North /  South Section Line  
3630 Feet from  East /  West Section Line  
Sec. 35 Twp. 12 S. R. 21  East  West  
County: Trego  
Date Well Completed: 10/07/1967  
Plugging Commenced: 08/17/2007  
Plugging Completed: 08/17/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-Kansas City	Oil & Water	3581'	3586'	8.625"	213'	-0-
OH Arbuckle	Oil & Water	3884'	3896'	5.50"	3884'	-0-
Ft. Scott	Oil & Water	4311'	4314'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8" tubing to 2198'. Pumped 100 sx 60/40 Pozmix w/10% gel + 200# hulls. Pulled tubing up to 1100'. Circulated to surface with 80 sx 60/40 Pozmix w/10% gel + 300# hulls. Pulled tubing out of hole. Pumped 130 sx 60/40 Pozmix w/10% gel + 400# hulls down 5 1/2" casing. Pumped 10 sx 60/40 Pozmix w/10% gel down annulus. Plugging complete on 08/17/2007, witnessed and approved by

Marvin Mills with the KCC Express Well Service & Supply Inc

Name of Plugging Contractor: Allied Cementing License #: 6426 RECEIVED KANSAS CORPORATION COMMISSION  
Address: P. O. Box 31 Russell, KS 67665 ACCEPT PER CP 2/3 AUG 28 2007  
Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc. 8/30/07 CONSERVATION DIVISION WICHITA, KS  
State of Kansas County, Trego, ss.

John Niernberger - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN TO before me this 27th day of August, 20 07

My Commission Expires: \_\_\_\_\_  
Notary Public

*PT*

# ALLIED CEMENTING CO., INC.

33321

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>8-17-07</u>	SEC. <u>35</u>	TWP. <u>12</u>	RANGE <u>21</u>	CALLED OUT	ON LOCATION	JOB START <u>4:35 PM</u>	JOB FINISH <u>5:35 PM</u>
LEASE <u>Deutcher</u>	WELL # <u>1-P</u>	LOCATION <u>Spot Riga I-70 Exit</u>		COUNTY <u>Trego</u>	STATE <u>KANSAS</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1/2 N 1 1/2 E 1/2 S INTO</u>			

CONTRACTOR Express Well Service  
 TYPE OF JOB PLUG ABANDONED Well  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 5 1/2 DEPTH 3884'  
 TUBING SIZE 2" DEPTH 2300  
 DRILL PIPE 8 5/8 Surface DEPTH 213  
 TOOL DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_  
 CEMENT (used 310SK)  
 AMOUNT ORDERED 350 SK 60% 10% G.  
900 # HULL'S

COMMON	<u>186</u>	@ <u>11.10</u>	<u>2064.60</u>
POZMIX	<u>124</u>	@ <u>6.40</u>	<u>768.00</u>
GEL	<u>16</u>	@ <u>16.65</u>	<u>266.40</u>
CHLORIDE		@	
ASC		@	
Hulls	<u>9</u>	@ <u>25.50</u>	<u>229.50</u>
HANDLING	<u>385 TOTAL SK.</u>	@ <u>1.90</u>	<u>731.50</u>
MILEAGE	<u>52 Ton mile</u>	@ <u>094</u>	<u>1301.88</u>
TOTAL			<u>5862.60</u>

EQUIPMENT

PUMP TRUCK CEMENTER Glenn  
 # 398 HELPER BOB  
 BULK TRUCK  
 # 396 DRIVER CHRIS  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

Ran 2" Tubing to 2300' Spot 100SK  
 Cement w/ 200# Hulls. Puled up to  
 1150' & circulated cement to surface  
 w/ 80SK & 300# Hulls. Came out w/ tubing  
 Hooked up to CSG w/ 5 1/2" Swagel & mixed  
 SK Cement w/ 400# Hulls.  
 8 5/8 Backside mixed 10 SK @ 200#  
 & shot in. THANKS

SERVICE

DEPTH OF JOB \_\_\_\_\_  
 PUMP TRUCK CHARGE 2nd well 720.00  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 52 @ \_\_\_\_\_ - NE -  
 MANIFOLD @ \_\_\_\_\_

CHARGE TO: RITCHIE EXPLORATION  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL 720.00

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 @  
AUG 28 2007  
 @  
 CONSERVATION DIVISION  
 WICHITA, KS  
 TOTAL \_\_\_\_\_

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Thomas Atkins → Thomas A Atkins  
 PRINTED NAME