

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: SWD Docket #: D-21-146
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 08/17/2007 (Date)
by: Marvin Mills (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Cedar Hills Depth to Top: 1442' Bottom: 1505' T.D. 1810'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-21041-00-01
Lease Name: Hillman
Well Number: 7 SWD KCCPKT 8/30/07 Per CP2/3
Spot Location (QQQQ): SE - SE - SE - NE/4
2440 Feet from North / South Section Line
100 Feet from East / West Section Line
Sec. 35 Twp. 11 S. R. 22 East West
County: Trego
Date Well Completed: 07/05/1982
Plugging Commenced: 08/17/2007
Plugging Completed: 08/17/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cedar Hills	Water	1442'	1505'	8.625"	169'	-0-
				4.50"	1803'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8" tubing to 1412'. Pumped 50 sx 60/40 Pozmix w/10% gel + 200# hulls. Pulled tubing up to 700'. Circulated to surface with 20 sx 60/40 Pozmix w/10% gel + 100# hulls. Pulled tubing out of hole. Pumped 5 sx 60/40 Pozmix w/10% gel down 4 1/2" casing.

Plugging complete on 08/17/2007, witnessed and approved by Marvin Mills with the KCC

*KCCPKT 8/30/07
per CP2/3*

Name of Plugging Contractor: Express Well Service & Supply Inc License #: 6426
Allied Cementing License #: _____
Address: P. O. Box 31 Russell, KS 67665

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Trego, ss.

AUG 28 2007

CONSERVATION DIVISION
WICHITA, KS

John Niernberger - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN TO before me this 27th day of August, 20 07

My Commission Expires: _____
Notary Public

PKS

ALLIED CEMENTING CO., INC.

33320

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>8-17-07</u>	SEC. <u>35</u>	TWP. <u>11 SWD</u>	RANGE <u>22</u>	CALLED OUT	ON LOCATION	JOB START <u>10:30AM</u>	JOB FINISH <u>11:00AM</u>
LEASE <u>Hillman</u>	WELL # <u>7</u>	LOCATION <u>Ogallah 3N 1E 1/2N</u>			COUNTY <u>Trego</u>	STATE <u>KANSAS</u>	
<u>OLD</u> OR NEW (Circle one)							

CONTRACTOR Express Well Service
 TYPE OF JOB old hole plug
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2 DEPTH 1803'
 TUBING SIZE 2 3/8 DEPTH 1400'
 DRILL PIPE 8 5/8 DEPTH 169'
 TOOL _____ DEPTH _____
 PRES. MAX 500# MINIMUM 500#
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER (USED 75 SK)
 CEMENT AMOUNT ORDERED 150SK 60% 10% GEL

300 # Hulls

COMMON	<u>45</u>	@ <u>11.10</u>	<u>499.50</u>
POZMIX	<u>30</u>	@ <u>6.20</u>	<u>186.00</u>
GEL	<u>6</u>	@ <u>16.65</u>	<u>99.90</u>
CHLORIDE		@	
ASC		@	
<u>Hulls</u>	<u>3</u>	@ <u>25.50</u>	<u>76.50</u>
		@	
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>159 TOTAL SK</u>	@ <u>1.90</u>	<u>302.10</u>
MILEAGE	<u>57 Ton Mile</u>	@ <u>.09¢</u>	<u>513.00</u>
TOTAL			<u>1979.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Allen
 # 398 HELPER BOB
 BULK TRUCK
 # 396 DRIVER CHRIS
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:
Ran 2" Tubing To 1400' Spdt 50SK
Cement w/ 400# Hulls, pulled up to
700' & CIRCULATED cement TO
SURFACE w/ 20 SK (100) pulled 2"
TUBING, Hooked up to 4 1/2 CSG
w/ SWAGE & Squeezed in
ANOTHER 5 SK @ 500# MAX
& SHUT IN @ 500#
8 3/8 BCKS. COULD NOT PUMP INTO. THANK'S

SERVICE

DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____ 815.00
 EXTRA FOOTAGE @ _____
 MILEAGE 57 @ 6.00 342.00
 MANIFOLD @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 TOTAL 1157.00

CHARGE TO: RITCHIE EXPLORATION
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas Atkins Thomas A Atkins
 PRINTED NAME

RECEIVED
 KANSAS CORPORATION COMMISSION
 AUG 28 2007
 CONSERVATION DIVISION
 WICHITA, KS