

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

AUG 29 2007

Form CP-4
December 2003

CONSERVATION DIVISION
WICHITA, KS
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: The Dane G. Hnsen Trust
Address: P. O. Box 187, Logan, KS 67646
Phone: (785) 689-4816 Operator License #: 5285
92,390-C
Type of Well: SWD Docket #: (C-16,127)
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: August 24, 2007 (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-20445-00-01
Lease Name: Wilson 'K'
Well Number: 4
Spot Location (QQQQ): E/2 - SW - SW -
660 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 32 Twp. 8 S. R. 23 East West
County: Graham
Date Well Completed: Spud 5/1/71
Plugging Commenced: 11:00 A.M. 8/24/07
Plugging Completed: 12:00 A.M. 8/24/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	204'	None
				4 1/2"	2000'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8" tubing to 1200' Circulated cement to surface w/80 sks and 500# Hulls.
Pulled tubing and hooked up to 4 1/2" casing w/swage. Squeezed in another 20 sks
@ 500#, Shut:in @ 500#. 8 5/8" backside could not pump into @ 1000#.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996 Per Lic.
Address: P. O. Box 31, Russell, KS 67665
Name of Party Responsible for Plugging Fees: The Dane G. Hansen Trust, P. O. Box 187, Logan, KS 67646
State of Kansas County, Phillips, ss.

Richard L. Wallgren, Sr. (Employee of Operator) or (~~Operator~~) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] Richard L. Wallgren, Sr.
(Address) P. O. Box, Logan, KS 67646

SUBSCRIBED and SWORN TO before me this 27 day of August, 20 07



[Signature] My Commission Expires: July 17, 2008

W E L L L O G

OPERATOR: DANE G. HANSEN TRUST
WELL NAME: WILSON "K" #4 LOCATION: E/2 SW SW SEC 32-8-23W
COUNTY: GRAHAM STATE: KANSAS
WELL COMMENCED: MAY 1, 1971 WELL COMPLETED: MAY 7, 1971
ELEVATION: 2337 KB TOTAL DEPTH: 3876'
PRODUCTION: DRY & ABANDONED RIG NO: 1
CASING - 8-5/8": 10 JTS, 204.45' USED 28# 8 5/8" CASING W/160 SX QUICKSET
5-1/2":

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	40	SAND		
40	204	SHALE		
204	1500	SHALE & SAND	1/4° @ 500'	
1500	1750	SAND	1/2° @ 1090'	
1750	1998	RED BED		
1998	2035	ANHYDRITE		
2035	2730	SHALE	1 1/4° @ 2680'	
2730	3876	LIME & SHALE		DST #13797'-3876'
3876		RTD		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 29 2007

CONSERVATION DIVISION
WICHITA, KS

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway

G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 7th day of May, 1971.



Phyllis Buchanan
PHYLIS BUCHANAN - NOTARY PUBLIC