

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mai Oil Operations, Inc.
Address: P.O. Box 33, Russell, Ks. 67665
Phone: (785) 483-2169 Operator License #: 5259
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-22-07 (Date)
by: Bruce Baseye (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet) _____
LKC, Plattsmouth Depth to Top: 2870' Bottom: 3232' T.D. 3280'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-03222-00-00
Lease Name: Schauf "C"
Well Number: 5
Spot Location (QQQQ): SW - SE - NW -
2970 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 1 Twp. 16 S. R. 12 East West
County: Barton
Date Well Completed: 2-12-64
Plugging Commenced: 8-23-07
Plugging Completed: 8-23-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	296'	Cemented
				5 1/2"	3314'	NONE


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg. to 2800', Mix & spot 100 sks and 500# Hulls, pull tbg. to 1800', mix & spot 100 sks and 300# hulls, pull tbg. to 400' circ 5 1/2" csg. w/50 sks & 200# hulls. POH w/ tbg., hookup to 5 1/2" circ cement 8 5/8" w/50 sks. hole stayed full. All cement 60-40 POZ, 10% GEL

RECEIVED
KANSAS CORPORATION COMMISSION
Express Well Service & Supply Inc
Name of Plugging Contractor: Allied Cementing License #: 6420 **AUG 29 2007**
Address: 24 S. Lincoln, Russell, Ks. 67665
CONSERVATION DIVISION
WICHITA KS

Name of Party Responsible for Plugging Fees: Mai Oil Operations, Inc.
State of Kansas County, Russell, ss. KCC PPT 9/5/07
Allen Bangert (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Allen Bangert
(Address) P.O. Box 33, Russell, Ks. 67665



SUBSCRIBED and SWORN TO before me this 27 day of August, 2007
Brenda Hall My Commission Expires: 3-21-07
Notary Public

Handwritten initials