

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20639-00-00  
Spot: W2SESWNE Sec/Twnshp/Rge: 27-9S-20W  
3300 feet from S Section Line, 1750 feet from E Section Line  
Lease Name: RATHBUN Well #: 9  
County: ROOKS Total Vertical Depth: 3820 feet

Operator License No.: 33306  
Op Name: BLAKE EXPLORATION, LLC  
Address: 201 S. MAIN PO BOX 150  
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3932	0	w/150 sxs cmt
SURF	8.625	269	0	w/160 sxs cmt

\$ 124.15

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2007 9:30 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: MICHAEL DAVIGNON Company: BLAKE EXPLORATION, LLC Phone: (785) 421-2921

Proposed Plugging Method: Ordered 375 sxs 60/40 pomix - 10% gel - 800# hulls.  
Permission granted to plug with rig over the hole.  
Squeezed with 300 sxs common - 1600' to 1650' w/1000# pressure.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2007 12:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:  
Ran tubing to 3519' - spotted 150 sxs 60/40 pozmix - 10% gel with 200# hulls - 500# pressure - had circulation.  
Pulled tubing to 1500' - pumped 80 sxs 60/40 pozmix - 10% gel w/250# hulls - 500# pressure - circulated cement.  
Pulled all tubing - pumped 35 sxs 60/40 pozmix - 10% gel down casing. S.I.P. 650#.  
Pumped 50 sxs 60/40 pozmix - 10% gel with 150# hulls. - 300# pressure.

Perfs:  
**INVOICED**  
DATE 9-4-07  
INV. NO. 2008060335

RECEIVED  
KANSAS CORPORATION COMMISSION  
**AUG 29 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.  
Plugged through: TBG

District: 04 Signed Pat Bedore PIRT I  
(TECHNICIAN)

**AUG 24 2007**

*PKT*

SOUTHERN STATES OIL CO.  
P.O. BOX 1365

#9 RATHBUN

27-9-20W  
W/2 SE SW NE

GREAT BEND, KS.

CONTR DUKE DRILG. CO.

CTY ROOKS

GEOL STEVE POWELL

FIELD NORTHAMPTON

E 2291 KB CM 9/27/76 <sup>CARD</sup> ISSUED 11/18/76 P 50 BOPD N/W

+	+
+	+
+	+

API 15-163-20,639

SMP	TOPS	DEPTH	DATUM
ANH	1757	+ 534	
HEEB	3497	-1206	
TOR	3520	-1229	
LKC	3536	-1245	
BKC	3759	-1468	
CONG	3830	-1539	
ARB	3836	-1545	
RTD	3933	-1642	

8-5/8" 269/160sx, 5 1/2" 3932  
NO LOG  
NO DST'S  
MICT - PF 3869-3872 (ARB) SWB 1 BOPH,  
NAT, AC 100, REC LD, SWB 20 BOPH, N/W.  
POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS