

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21302-00-00
Spot: SESWSW Sec/Twnshp/Rge: 11-15S-14W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: KRUG LYDIA Well #: 2
County: RUSSELL Total Vertical Depth: 3326 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3323	0	w/75 sxs cmt
SURF	8.625	861	0	w/400 sxs cmt

108.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/24/2007 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-2719

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2007 2:35 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Well Service sanded off bottom to 3260' and topped with 5' sxs cement using a dump bailer.
Cut casing at 1840' - pulled to 1625'.
Quality Well Service rigged to 5 1/2" casing - pumped 145 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled casing to 900'. Quality Well Service rigged to casing - pumped 40 sxs 60/40 pozmix with 100# hulls.
Pulled casing to 200' - Quality Well Service rigged to casing - spotted 45 sxs 60/40 pozmix - 4% gel.
Pulled casing. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3323	3326		Arbuckle

INVOICED
DATE 9-4-07
INV. NO. 2008060336

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 29 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING-TICKET #1584.

Plugged through: CSG

District: 04

10

Signed [Signature]
(TECHNICIAN)

AUG 27 2007

PS

