

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23328-00-00
Spot: NWSESE Sec/Twnshp/Rge: 34-6S-24W
1010 feet from S Section Line, 1090 feet from E Section Line
Lease Name: STORZ Well #: 1
County: GRAHAM Total Vertical Depth: 4047 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	317		

\$131.53

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/17/2007 3:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: FRANK ROME Company: PALOMINO PETROLEUM, INC. Phone: (316) 799-1000

Proposed Plugging Method: Ordered 195 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 08/17/2007 4:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st. Plug at 2250' w/25 sxs.
2nd. Plug at 1325' w/100 sxs.
3rd. Plug at 375' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 9-4-07
INV. NO. 2008060339

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Darrel Dipman
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 27 2007

CONSERVATION DIVISION
WICHITA, KS

AUG 17 2007

PT