

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01007-00-02
Spot: NESESW Sec/Twnshp/Rge: 3-10S-21W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MILLER Well #: 4
County: GRAHAM Total Vertical Depth: 915 feet

Operator License No.: 32705
Op Name: RANEY OIL COMPANY, LLC
Address: 3425 TAM O'SHANTER
LAWRENCE, KS 66047

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265	0	w/unknown sxs cmt

\$ 35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2007 8:45 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: IRVIN HASELHORST Company: RANEY OIL COMPANY, LLC Phone: (785) 749-0672

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.
Alliance Well Service drilled to 915' and lost the hole.
Emergency plug with rig over the hole.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2007 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

RIH with tubing to 380'. Tubing stacked out.
Allied rigged to tubing and pumped 200 sxs 60/40 pozmix - 4% gel - good circulation - no cement circulated to surface.
Operator ordered an additional 150 sxs 60/40 pozmix - 4% gel.
Let set two hours.
RIH with tubing to 160'. Tagged cement.
Allied rigged to tubing and pumped 50 sxs 60/40 pozmix with 150# hulls mixed in to circulate cement to surface.
Pulled tubing. Hole standing full.

INVOICED
DATE 9-4-07
INV. NO. 2008060341

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 29 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33155.

Plugged through: TBG

District: 04

140

Signed 
(TECHNICIAN)

Pat