

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21331-00-00
Spot: NWNENE Sec/Twnshp/Rge: 25-20S-16W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: CJMA Well #: 1-25
County: PAWNEE Total Vertical Depth: 3899 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3898	1400	WITH 135 SX CMT
SURF	8.625	1039		WITH 375 SX CMT

\$126.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2007 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KIRK GLENN Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND BACK TO 3700' WITH 5 SX CMT. PLUG AT 1070' WITH 10 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 30' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND
Date/Time Plugging Completed: 08/15/2007 11:35 AM

Witness Type: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3700' & 5 SX CMT. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1060' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3764	3768		


INVOICED
DATE 9-4-07
INV. NO. 2008060344

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 28 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

Form CP-23

[Handwritten initials]