

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-02123-00-00

Spot: SENESE

Sec/Twnshp/Rge: 2-34S-5E

1792 feet from S Section Line,

441 feet from E Section Line

Lease Name: HART

Well #: 2

County: COWLEY

Total Vertical Depth: 3118 feet

Operator License No.: 33608

Op Name: W.D. SHORT OIL CO., LLC

Address: 102 S. RIVER ROAD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3099	840	125 SX CMT
SURF	8.625	97		90 SX CMT

\$ 101.34

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/17/2007 8:00 AM

Plug Co. License No.: 32475

Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C

Proposal Rcvd. from: JIM BRADEN

Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed
Plugging
Method:

PER KCC RULES & REGS.

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/22/2007 2:30 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-17-2007, SANDED BACK @ 3045', DUMP BAILED 4 SXS CEMENT ON TOP.
04/20/2007, SHOT 4-1/2" CASING @ 840', LAYED DOWN 4-1/2" CASING. 5-22-2007,
RIH W/TG @ 250', BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED
100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN
1445, 05-22-2007. CEMENT TICKET #07-575.

Perfs:

Top	Bot	Thru	Comments
3097	3118		

INVOICED
DATE 9-10-07
INV. NO. 2008060372

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.84337,37.11841, OH 3097'-3118'

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)