

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22980-00-00
Spot: E2W2SE Sec/Twnshp/Rge: 16-31S-11W
1280 feet from S Section Line, 1690 feet from E Section Line
Lease Name: ELAINE Well #: 1
County: BARBER Total Vertical Depth: 5030 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments	
CIBP		4600			\$163.48
PROD	4.5	5016	3591	WITH 200 SX CMT	
SURF	8.625	375		WITH 275 SX CMT	

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/07/2007 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: AL BALMARO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4460' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2007 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4400' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. **SPOT PLUGS THROUGH 4 1/2" CASING. SPOT PLUG AT 1890' DUE TO ATTEMPT TO BLOW OUT.** 1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 3RD PLUG AT 400' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4874	4877		
4515	4525		


INVOICED
DATE 9-10-07
INV. NO. 2008060363

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 30 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)