

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21942-00-00

Spot: SENENW

Sec/Twnshp/Rge: 34-23S-30W

860 feet from N Section Line,

2360 feet from W Section Line

Lease Name: PAMELA

Well #: 1

County: FINNEY

Total Vertical Depth: 4850 feet

Operator License No.: 5663

Op Name: HESS OIL COMPANY

Address: PO BOX 1009  
MCPHERSON, KS 67460

String Size Depth (ft) Pulled (ft) Comments

SURF 8.625 346

WITH 190 SX CMT

\$157.63

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/17/2007 4:00 PM

Plug Co. License No.: 4958

Plug Co. Name: MALLARD, J. V., INC.

Proposal Rcvd. from:

Company:

Phone:

Proposed Plugging Method: 1ST PLUG AT 2000' WITH 50 SX CMT. 2ND PLUG AT 1150' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 370' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER

Witness Type: NONE

Date/Time Plugging Completed: 08/17/2007 6:00 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 2000' WITH 50 SX CMT. 2ND PLUG AT 1150' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 370' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

INVOICED

DATE

9-10-07

INV. NO.

2008060365

RECEIVED  
KANSAS CORPORATION COMMISSION


AUG 30 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

Form CR-27