

API NUMBER 6-28-69

LEASE NAME Lackey

WELL NUMBER 1

 Ft. from S Section Line

SW-SE-SW Ft. from E Section Line

SEC. 14 TWP. 28S RGE. 3E (E) or (W)

COUNTY Butler

Date Well Completed 7-4-69

Plugging Commenced 6-10-97

Plugging Completed 6-12-97

TYPE OR PRINT
 NOTICE: Fill out complotoly
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR P.E.P.

ADDRESS Box 20 Russell, Ks 67665

PHONE# (913) 483-6144 OPERATORS LICENSE NO. 3018

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-10-97

by Jerry Clark

(KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached? Yes

Producing Formation Simpson Depth to Top 2984' Bottom 2986' T.D. 2986'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	182'	None
				5 1/2	2979'	999'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. 15 sax cement at 2950' through tubing, pull pipe to 250 and pump 85 sax cement to G. L.

Shot pipe at 1987', 1497', and 999'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor George Sage License No. 5684

Address Box 12 Virgil Ks. 66870

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Fred Weigel, JR Box 878 Russell, Ks. 67665

STATE OF Kansas COUNTY OF , ss.

George Sage (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) George Sage

(Address) Box 12 Virgil, Ks. 66870

SUBSCRIBED AND SWORN TO before me this 2nd day of Sept, 1997

My Commission Expires: 4/24/2001

Kelly Sage
 Notary Public



KANSAS CORP COMM
 RECEIVED
 9/18/97

508 East Murdock
Wichita, Kansas

SEP 27 1969

K. G. S. LIBRARY

ORIGINAL

15-015-20270-00-00
14-28-3E

DRILLERS LOG

#1 LACKEY

CASING RECORD:	COMPANY:	Kathol Petroleum, Inc.	DESCRIPTION:
8 5/8" set @ 182' w/273 sacks cem.	CONTRACTOR:	Kathol Petroleum, Inc.	SW SE SW Sec. 14-28S-3E Butler Co., Kansas
5 1/2" set @ 2979' w/50 sacks cem.	COMMENCED:	June 28, 1969	ELEVATION:
TOTAL DEPTH: 2986'	COMPLETED:	July 4, 1969	1320' DF 1323' KB
	I.P. 72 B.O.P.D. - No Wtr.		

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
surface soil	0	15	
lime & shale	15	182	
sand & shale	182	349	
lime w/hard flint rock strks.	349	615	
lime	615	1035	
shale w/lime strks.	1035	1455	
lime & shale	1455	2411	
lime	2411	2896	
shale	2896	2975	
lime	2975	2980	
shale	2980	2983	
sandy shale	2983	2984	
sand	2984	2986 T.D.	
<u>DDTD</u>		<u>2987 1/2</u>	<u>DDTD</u>

oil
Present
~~2984 47 ch~~
North 47 ch

I hereby certify that the above information is true and correct to the best of my knowledge.

CONSERVATION DIVISION
WICHITA, KS

SEP 18 1967

RECEIVED
KANSAS CORPORATION COMMISSION

KATHOL PETROLEUM, INC.

Don D. Shawver
Don D. Shawver

Subscribed and sworn to before me this 7th day of August, 1969.

Betty M. Maloney
Betty M. Maloney, Notary Public

My Commission Expires: