

15-015-00011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County, Sec. 19 Twp. 28 Rge. 3 (E) E ~~XX~~

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Francis Oil & Gas, Inc. and Herman George Kaiser
Lease Name Dennett Well No. 1
Office Address 905 Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 8 1955
Application for plugging filed August 8 1955
Application for plugging approved August 8 1955
Plugging commenced August 8 1955
Plugging completed August 8 1955
Reason for abandonment of well or producing formation Non-productive

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence Matthews
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3228 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	122	8-5/8	122	None - cement circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 3228' to 180'. Plug set 180'.
15 sacks cement. Plug set 20'. 5 sacks
cement to top of hole.

RECEIVED
STATE CORPORATION COMMISSION
8/17/55
AUG 17 1955

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallonee Drilling Company, Inc.
Address 812 Central Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Mallonee, employee of contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mallonee
812 Central Bldg., Wichita, Ks.
(Address)

August 16, 1955

Rosemary Penrose
Rosemary Penrose Notary Public.



SUBSCRIBED AND SWORN to before me this 16 th day of August, 1955

My commission expires March 30, 1957

PLUGGING
FILE SEC 19 28 R 3 E
BOOK PAGE 140 LINE 23

15-015-00011-00-00

DRILLERS' LOG
#1 Dennett
NE NE SW Section 19-28-3E
Butler County, Kansas

OWNER: Francis Oil & Gas, Inc. & Herman Geo. Kaiser

COMMENCED: 7-30-55

CONTRACTOR: Mallonee Drilling Company, Inc.

COMPLETED: 8-8-55

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>	<u>REMARKS</u>
0	40	Clay & Shale	
40	76	Sand & Gravel	
76	121	Lime & Shale	
			122' 8-5/8" 24# Surface Casing set at 121' with 75 sks common cement plus 1% calcium chloride. Cement circulated.
121	480	Lime & Shale	
480	485	Red Rock	
485	670	Shale	
670	730	Shale with lime streaks	
730	825	Lime	
825	860	Shale	
860	1240	Shale & Lime	
1240	1630	Shale & Shells	
1630	1755	Lime with shale breaks	
1755	1960	Lime and Shale	
1960	2100	Shale & Shells	
2100	2235	Shale, Shells & Lime	
2235	2405	Lime	
2405	2508	Shale & Lime	
2508	3160	Lime	
3160	3180	Lime, Sand & Shale	
3180	3228	Lime	
	3228	Total Depth of Hole	D & A

I certify that to the best of my knowledge and belief the foregoing represents a true and accurate Drillers' Log record of the captioned well.

P. E. Mallonee

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

Subscribed and sworn to before me this 15th day of August, 1955.

Raymond Penrose
Notary Public

My commission expires:
March 30, 1957

PLUGGING
FILE SEC 19 T 28 R 3E
BOOK PAGE 142 LINE 23